Mohawk Group Ш

Tuff Stuff II Collection

QL311 Step Up II Tile

Mohawk Group



DESIGN

Product Type:	Modular-Walk Off
Construction:	Tufted
Minimum Sq Yd:	No Minimum
Surface Texture:	Performance Tip Shear
Gauge:	5/32 (25.2 rows per 10 cm)
Tufted Pile Weight:	38.0 oz. per sq. yd. (1288 g/m2)
Finished Pile Thickness:	.144" (3.66 mm)
Stitches Per Inch:	8.5 (33.46 per 10 cm)
Dye Method:	Solution Dyed
Fiber Type:	Duracolor® Premium Nylon
Fiber Technology:	Duracolor® by Mohawk Group's Stain Resistant System. Passes GSA requirements for permanent stain resistant carpet.
Stain Release Technology:	Permanent, Built into Fiber
Soil Release Technology:	EcoSentry Soil Protection
Density:	9,500
Weight Density:	361,000
Backing Material:	EcoFlex NXT
Alternate Backing:	EcoFlex AIR - Minimum SY Required
Installation Method:	Quarter Turn, Monolithic, Brick Ashlar, Vertical Ashlar, Multi Directional
Size:	24" x 24" (.6096 m x .6096 m)
Pattern Repeat:	Not Applicable
SUSTAINABILITY	
Pre-Consumer Recycled Content:	53%
NSF 140:	EcoFlex NXT - NSF 140 Gold

PERFORMANCE

Indoor Air Quality:

Declare Label:

Flammability: Smoke Density: Static Propensity: Foot Traffic Recommendation TARR: GSA Stain Release Rating:

CRI Green Label Plus GLP1171 **Declared Red List Free**

ASTM E 648 Class 1 (Glue Down) Severe Pass

ASTM E 662 Less than 450 AATCC-134 Under 3.5 KV

SERVICE

Warranties:

Lifetime Limited Carpet Tile Warranty, Lifetime Duracolor Stain Warranty, Lifetime Static